



**AMENDMENT ON BID DOCUMENT OF INVITATION FOR BIDS NOTICE**

For

**Construction of Retaining Gabion wall structure of Mahuregadi Polytechnic of IFB number CTEVT/MPI/SQ/wroks/076/077/01**

(2<sup>nd</sup> Amendment Date: June 2<sup>nd</sup> 2020)

1. The **BOQ of IFB CTEVT/MPI/SQ/wroks/076/077/01** has been changed as below.

SN	Relevant Clause No./Name	Existing Clause	Modified details	Chapter
1	Revised Last date of submission	2020-06-03, 12:00	2020-06-05, 12:00	General Information
2	Revised Last bid opening date	2020-06-03, 13:00	2020-06-05, 13:00	General Information
3	GCC 1.1.12	18	16	SCC
4	GCC 2.1	21-06-2020	23-06-2020	SCC

2. The estimated amount, in the **Invitation for Sealed Quotation** section of the BID DOCUMENT, for the works is (NRs.): 1275836.93 (Exclusive of VAT, PS and contingencies) instead of old estimated amount for the works in Bid document of NRs. 1276033.91.

3. The revised BOQ will be as under:

Bill of Quantities						
S. N.	Description of work	Unit	Quantity	Rate		
				In Figure	In Words	Amount
Provisional Sum						
1	Supplying and Fixing of hodging Board(Displaying all the information regarding project as per site incharge)	L.S.	1	5000.00	Five Thousand only.	5000.00
Civil Works						
1	Earth work excavation in foundation in clay & soft murrum stone (30 cm.) hard soil lead upto 10 mtr. & lift 1.5 mtr.	Cum	45.60			
2	Fabrication of gabion boxes including rolling, cutting and weaving B. Hexagonal Mesh Size - 100 mm x 120 mm ii. Mesh wire - 10 SWG Selvedge wire - 7 SWG Box size (2m x1 m x1 m)	nos	111.00			
3	Assembling of wire crates /gabion/ revetment and placing them in position including stretching, binding them together and tying down lids i. Binding wire - 12 SWG Box size (2m x1 m x 1m)	nos	111.00			
4	Gabion wire Procurement (2*1*1) box Size	nos	111.00			
5	Packing and filling of gabion crates with rubble stones - Stone masonry work including full compensation for all labour, materials and other incidentals required to complete the work as per the Specifications and drawings. It includes full compensation for using specially dressed stones on the face of walls with batter and makes provision for weep holes as necessary.	Cum	222.00			
			<b>Sub Total Rs-</b>			
			<b>Vat 13 @ % Rs-</b>			
			<b>Grand Cost Rs-</b>	-		